




Crack Stitching

A reliable and cost-effective means of repairing and stabilising cracked masonry

APPLICATIONS

- Rapid and permanent solution to cracked masonry
- Suitable for all forms of masonry structure







Standard repair specifications are available online, covering common structural faults. **Relevant Repair Details: CS01 to CS03**



FEATURES

- Fully concealed, non-disruptive repair solution
- More reliable than crack injection methods
- HeliBond cementitious grout is injectable and rapidly produces high compressive strength
- HeliBars and HeliBond grout combine to create excellent tensile strength within the masonry
- No additional stresses are introduced during installation
- Masonry remains flexible enough to accommodate normal building movement
- Tensile loads are redistributed
- Reduces likelihood of further cracking nearby
- Avoids costly and disruptive taking down and rebuilding



HeliBar is inserted into HeliBond grout with a cut slot



For full product information, case studies and downloadable repair details go to: www.helifix.co.nz/products/remedial-products/crack-stitching/



TECHNICAL SPECIFICATIONS

CRACK STITCHING				
Material	Austenitic stainless steel Grade 316 (as standard)			
Diameter	6mm (as standard)			
Tensile strength (6mm HeliBar)	10 kN			
0.2% Proof stress (6mm HeliBar)	840N/mm ²			
Length	To extend 500mm either side of the crack or outer cracks, if more than one			
Standard lengths	1m and 7m. May be cut to length on site			
Height of slot	Full height of mortar bed or approx. 10mm if cut through the masonry unit			
Bonding agent	HeliBond cementitious grout. 1 x 4.5ltr HeliBond = ~15 linear metres of stitching			

RECOMMENDED TOOLING				
For cutting slot up to 40mm deep:	Twin-bladed cutter with vacuum attachment or angle grinder or hammer and mortar chisel			
For mixing HeliBond grout:	3-jaw-chuck drill with mixing paddle			
For injection of HeliBond into slots:	Helifix Pointing Gun CS with mortar nozzle			
For smoothing pointing:	Standard finger trowel			
For inserting HeliBar:	HeliBar insertion tool (finger towel or similar)			

SLOT DEPTH AND SPACING						
	Single skin/ Cavity wall	Solid Masonry				
		Up to 102.5mm	102.5mm to 225mm	Over 225mm		
Depth of slot	25 – 35mm		25 – 40mm	25 – 40mm on both sides		
Vertical spacing	Every 4 – 6 courses, 300 – 450mm					



PRODUCT SHEET PS/CS01

INSTALLATION PROCEDURES

- 1. HeliBar to be long enough to extend a minimum of 500mm either side of the crack or 500mm beyond the outer cracks if two or more adjacent cracks are being stitched using one rod.
- 2. Where a crack is less than 500mm from the end of a wall or an opening, the HeliBar is to be continued for at least 200mm around the corner and bonded into the adjoining wall or bent back and fixed into the reveal, avoiding any DPC.
- **3.** For solid masonry in excess of 225mm thick and in a cavity wall where both leaves are cracked, the wall must be crack stitched on both sides.
- **4.** If there is render, this thickness must be added to the depth of slot. Crack stitching must be installed in the masonry and never in the render.
- 5. Ensure the masonry is well wetted or primed to prevent premature drying of the HeliBond due to rapid de-watering, especially in hot conditions. Ideally additional wetting of the slot should be carried out 1 to 2 minutes prior to injecting the HeliBond grout.
- Do not use HeliBond when the air temperature is +4°C and falling or apply over ice. In all instances the slot must be thoroughly damp or primed prior to injection of the HeliBond grout.








- Rake out or cut slots into the horizontal mortar beds, a minimum of 500mm either side of the crack.
- Clean out slots and flush with clean water and thoroughly soak the substrate within the slot.
- Using the Helifix Pointing gun, inject a bead of HeliBond along the back of the slot.

Using the HeliBar

insertion tool, push one

HeliBar into the grout





- Insert a further bead of HeliBond over the exposed HeliBar, finishing 12mm from the face, and 'iron' firmly into the slot using the HeliBar insertion tool.
- 6. Re-point the mortar bed and make good the vertical crack with CrackBond TE3.

